

6/5/01
Layout
11:00
8/3/01
Pump Test - AM
6/11/01
C.O.
ASAD

01-89050
PERMIT

515267

SEWAGE DISPOSAL SYSTEM
HOWARD COUNTY HEALTH DEPARTMENT
BUREAU OF ENVIRONMENTAL HEALTH
410-313-2640

P
A 512017

ISSUE DATE 5/31/01

APPROVAL DATE 8/3/01

INDEXED

(Dave Tolley-installer) Wilcom Homes, Inc IS PERMITTED TO INSTALL X ALTER

ADDRESS 407 Copper Oaks Place, Woodsboro, MD 21798 PHONE 301-898-0371

UBDIVISION Stottlemeyer Property LOT NUMBER 2 ADDRESS 1834 Long Corner Road

PROPERTY OWNER Ken Payne PROPERTY OWNER'S ADDRESS 11320 San Andrews Drive
New Market, MD 21774

EPTIC TANK CAPACITY 1250 GALLONS *Watertight septic tank required*

UMP CHAMBER CAPACITY 1250 GALLONS **WATERTIGHT PUMP CHAMBER REQUIRED**

NUMBER OF BEDROOMS 4

SQUARE FEET PER BEDROOM 210

LINEAR FEET OF TRENCH REQUIRED 280

TRENCHES: Trenches to be 3 feet wide. Inlet 4 feet below original grade. Bottom maximum depth
6 feet below original grade. 2 feet of stone below distribution box.

LOCATION: Starting at the lot corner at the end of the driveway, place the distribution
box 250 feet up the 408.04' lot line and 180 feet off this same lot line. Run 3 trenches
on contour toward the 408.04' lot line. 1/2/01 OK (RB)
Suggested layout: 80', 95', 105'

PLANS APPROVED Mark Rifkin, R.S. DATE 1/2/2001

- PERMIT VOID AFTER 2 YEARS
- NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS
- NOTE: TOP OF SEPTIC TANKS ARE TO BE NO DEEPER THAN 3.0 FEET BELOW FINISH GRADE
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: CLEANOUT REQUIRED EVERY 70 FEET OF SEWER LINE AND/OR AT 90° SWEEPS IN LINES FROM HOUSE TO DRAIN FIELDS, 90° ELBOWS ARE NOT ACCEPTABLE
- NOTE: ALL PARTS OF SEPTIC SYSTEMS (I.E. TANK, DISTRIBUTION BOX, DRAINFIELDS) TO BE 100 FEET FROM ANY WATER WELL UNLESS OTHERWISE SPECIFICALLY AUTHORIZED
- NOTE: NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH UNLESS SPECIFICALLY AUTHORIZED
- NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 35/40 PVC OR ABS
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS
- NOTE: DISTRIBUTION BOXES MUST HAVE BAFFLES
- NOTE: IF PUMPED SEPTIC SYSTEM REQUIRED, (1) SEPTIC PUMP DETAIL TO BE PROVIDED BY INSTALLER PRIOR TO ISSUANCE OF SEPTIC PERMIT (2) PUMP PERFORMANCE TEST IS NECESSARY PRIOR TO HEALTH DEPARTMENT APPROVAL OF SEPTIC PERMIT

PS15267

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE
SUCCESSFUL OPERATION OF ANY SYSTEM
PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT
CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM

